


# i-Repeater


Control and monitor all your repeaters through the cloud



Wallmount



Rackmount



Cloud control and monitoring  
Touch screen interface  
Alarms  
Statistics



\*Device = any repeater or line-amp

## Connection to the internet.

Each device MUST have a CAT5 ethernet cable connected to it for monitoring.

Option #1: These Cat5 cables are installed back to a comon 3G/4G router with a SIM card.  
This solution means you are independent of the buildings WIFI/Internet.

Option #2: Plug each device directly into the building network. No Setup (port forwarding) required. This way is easier but you are dependent on the building network.

## What monitoring offers you

Registered users (You, Stelladoradus, your client (Hotel)) can monitor and control devices in the building.

### Alerts:

You can enable 2 primary email alerts:

Alert 1: If devices are plugged out by accident by building staff (or power cut). (You can see the exact device that is plugged out, and its location in the building). All devices have internal battery that keeps internet connection live for several hours.

2: If devices are strongly attenuating RF due to local RF noise or disturbance, system will alert you. Example: big microwave ovens in a buildings have been known on rare cases to cause RF issues in local vicinity.

### Remote Control from any computer/ phone:

- Switch Off/ On/ or Attenuate, individual bands of any device.
- Switch off Power to one or all devices in a building. The devices RF chain is switched off but it is still connected to the internet.
- Reboot devices.

### Monitor:

- Up/Downlink Power
- Up/Downlink Gains
- Up/Downlink AGC
- Up/Downlink Oscillations/feedback
- Temperature on PCB board

### History:

- All events are logged from initial installation date for each device.
- A long term history graph for Power levels per band. This will allow you to see the effects of atmospheric conditions, or other conditions on the overall system over 1 year. (in development)
- Percentage usage of each band. Example:  
800Mhz :60%, 900Mhz :20%, 1800Mhz :5%, 2100Mhz:15% ,2600Mhz :0%

### Security and cloud:

The application infrastructure is physically located in AWS (Amazon Web Services) data-center in Europe (Ireland). AWS allows us to benefit from the most stringent security standards AWS holds for their infrastructure and allows one to satisfy many compliance requirements. More information on compliance with standards can be found in the AWS Security Whitetepaper at <https://aws.amazon.com/whitepapers/>.

### Updates:

Server software is tested and updated from time to time. This is only feasible when all services reside under the one server.


### Basic kit includes:

- 1 i-Repeater\_LGDWH,
- 4 internal antennas, 1 external Yagi antenna
- 4 lengths of SD240 cable (15m)
- 1 length of SD400 external cable
- 1 12v, 5A power supply (surge protected and tested)

The system can be extended using more repeaters and line amps to ensure converage in even the largest of multi-storey buildings.


### Logo:

Display your company logo to the LCD screen. This will be shown on the standby screen until a user touches the screen.



Example system for larger building

i-repeater and 4 X lineamps all internet controlled  
For even more coverage, duplicate this system




16 internal antennas - Coverage 1000m2 X 16

# TouchScreen Panel




When you turn on the repeater, you will see the main screen.  
The green signal LEDs signify the downlink signal strength for each band.  
6 green LEDS = max power.

If a blue LED lights up, that means that band is currently active. (Band 1800Mhz is currently active in the image)  
If there are no blue LEDs on , this means the repeater is in standby mode. (no uplink power)



Click the menu button

System - access to system settings  
Reboot - reboot repeater  
About - Serial, model, counters, time.



System Password: 1321

Power levels - View Power, AGC, Oscillation  
Factory reset - Clear counters, location memory  
Manual input - Control gains (MGC)  
Enter location (internal location of device in building)

## Power levels screen:

-Power Levels dBm  
-AGC (Automatic gain control) (temp and phone)  
-MGC (Manual gain control) User controlled  
-Osc (Feedback/ oscillation)

Frequency(Mhz)	800	900	1800	2100	2600
Power up (dBm)					
Power dn(dBm)					
Temp up(dB)					
Temp dn(dB)					
Phone up(dB)					
mgain up(dB)					
mgain dn(dB)					
Osc up(dB)					
Osc dn(dB)					


menu

## Manual Switch On/Off/attenuation screen:

Manually edit the Bands (use only when not connected to internet)

(You can only edit the bands when you are NOT connected to the internet-Plug out cat5 cable)


Touch switches to turn bands on or off.  
Touch the attenuator slider to add attenuation to any band.  
When repeater is connected to the internet, the cloud server will override your settings.



## Location:

Enter the location of the repeater. This is important for when you monitor all your repeaters on the website dashboard at a later stage.

Example: Floor 3, Section A, Meeting room






Login to your dashboard: [www.stellacontrol.com](http://www.stellacontrol.com)  
Enter your username and password.

## Step 1: Register your new i-repeater

Click Stock devices.  
Click Add device  
Enter the serial number of your repeater and click Find.  
Click Add Device

### Adding new device



Please enter serial number from the device


Please type serial you can find on the back of your device

Find

Cancel

## Step 2: Create a new building.


Click Buildings  
Click Add building  
Enter the data for your new building. Click Save.



## Step 3: Add your device to your building.

Click Stock devices.  
Click the Link button next to your new device.  
Using the drop down menu, select your building.  
Click Confirm and Link.

### Linking device **test4** to a building




Next


Cancel

## Thats it!

You can now monitor and control your device over the dashboard.  
The Live Status tab shows you exactly what the repeater sees.  
You can switch off the bands, add attenuation, monitor if any repeaters have lost power, plus more..



# Specification



Model number:	i4-LGDWH
Frequency:	800/900/1800/2100/2600
Remote monitoring:	Yes

## Frequency Specifications:

Frequency bands(Mhz):	(791-862) + (880-960) + (1710-1880) + (1.92-2.17) + (2500-2690)
Coverage:	(1000m <sup>2</sup> per antenna X 4) = ~15 rooms
Number of People:	Unlimited
Gain:	Uplink Gp > 50dB      Downlink Gp> 60dB
Pass band ripple:	< 4dB
I/O impedance:	50 ohm/SMA female connector
Max uplink/downlink signal strength:	19dBm / 10dBm
Ambient Temperature:	-30°C to +70°C
Power supply input:	110 - 240V AC
Power supply output:	12v DC
Oscillation Control	Automatic
Level Control:	Automatic*
Uplink Switch Off	Yes**
AGC Range	30db
Surge protection	SMA connectors DC grounded, 12V DC port MOV protected

## Antenna Specifications:

### Indoor antenna

### Outdoor antenna

Nominal Gain	6.4dBi / 9.4dBi	10dBi
3dB beam Pattern	60° x 60°	60° x 50°
Bandwidth	790-960MHz + 1710-2700MHz	790-960MHz + 1710-2700MHz
VSWR	<1.4	<1.5
Front to Back Ratio	> 20dB	> 20dB
Polarization	Vertical	Vertical
Power Rating	50W	50W
Impedance	50-OHM	50-OHM
Termination	SMA male	N-Female
Cross Pol. Discrimination	-20dB	-20dB
Dimensions	210 x 180 x 43mm	442 x 205 x 62mm
Weight	0.68kg	1.2kg
Wind velocity	126km/hr	140km/hr
Working temperature	-40°C to +65°C	-40°C to +65°C

## Power Supply Specification:

AC	100-240V	50-60Hz
DC input	12V	3.6A
Typical power usage		33W

## Mechanical Specification:

Length	35cm
Width	30cm
Depth	4.4cm
Weight	2kg
Mounting	6 x 5mm holes for mounting

\* Automatically adjusts during installation. Thereafter, automatically adjusts for seasonal variation in pathloss between basestation and outdoor antenna.

\*\* The up-link amplifiers switch off when the repeater is not in use. This reduces the uplink noise to almost zero. When the repeater is in use (eg. phone call being made), the up-link amplifier switches on for the duration of the call and a blue LED switches on indicating this is the case.

Note: Specifications subject to change without notice.

